



February 22, 2024

To: All Interested Parties

RE: Request for Proposal for Asphalt Overlays – March 2024

The City of Moscow Mills will receive sealed proposals for asphalt overlays until 3:00 p.m. CDT on Wednesday, March 6, 2024. All bids will be publicly opened at approximately 3:01 p.m. on Wednesday, March 6, 2024.

Mail or hand deliver proposals to:

Linda Haynes, City Clerk

Moscow Mills City Hall

PO Box 36

995 Main Street

Moscow Mills, MO 63362

The sealed envelope shall be plainly marked: Moscow Mills Asphalt Proposals – March 2024.

Questions or requests for additional information should be directed to Public Works Superintendent, Rob Hamlin at 636-290-5465 or [rhamlin@moscowmillsmo.com](mailto:rhamlin@moscowmillsmo.com)

Thank you for your interest.

Sincerely,

**Rob Hamlin**

Public Works Superintendent

City of Moscow Mills

## **Asphalt Overlays**

Required Work for each street:

1. Sweeping of surface.
2. Provide and install valve boxes or adjust the height of valve boxes at the time of overlay work.
3. Provide, place, and compact wedge asphalt course as needed.
4. Provide, place, and finish with depth as noted of compacted Type C Asphaltic Concrete Pavement over the entire street, from the edge of the street or the concrete gutter.
5. Tack Coat is an incidental item.
6. Mill butt joints at start and ends of overlays and at intersections with previously paved streets and driveway aprons.
7. Provide City with at least 48 hours of notice prior to starting work on any street.
8. Where identified by City and where possible, contractor shall lay asphalt adjacent to connecting sidewalks in a manner that minimizes changes in slope and does not create additional barriers to handicapped accessibility.
9. Millings will be delivered to the City Maintenance Department located at 500 State Hwy. MM in Moscow Mills.

Provided by City:

1. Notify residents and businesses to allow removal of vehicles prior to starting work.
2. Pavement of any transitions to driveway or side streets, when such transition extends more than two feet from the nominal edge of the overlay.
3. Adjustment of height of sewer manholes prior to Contractor's commencement of work.

### **Project locations & Work to be completed.**

Briarwood Subdivision:

Edge mill 2" at curb 7' wide and butt joint at Hampel Road. Then clean, tack, and place 2" overlay with MODOT BP-2. (approximately 4,277 square yards)

Monterey Estates:

Mill 2" joint at curb 7' wide and butt joint at Tropicana Village Drive and Santa Cruz Drive. Then clean, tack, and place 2" overlay with MODOT BP-2. (approximately 3,033 square yards)



Briarwood Subdivision





Monterey Estates (Eldorado Drive)